

FLUROPON®

CERTIFIED LABORATORY TEST REPORT

ACCELERATED WEATHERING QUV-A

TEST PROCEDURES:	ACCELERATED WEATHERING 5000 HOURS QUV-A, 340 NM BULB ASTM D 4587, ASTM G 154
PRODUCT TESTED:	FLUROPON [®]
TEST RESULTS:	ACCEPTABLE
FILM INTEGRITY:	NO CRACKING, PEELING, BLISTERING LOSS OF ADHESION OF THE COATING
CHALKING:	CHALK RATING OF 6 PER ASTM D 4214, METHOD A
COLOR CHANGE:	NO MORE THAN 5 Δ E HUNTER UNITS PER ASTM D 2244
LOCATION:	THE SHERWIN-WILLIAMS COMPANY FT. MYERS, FLORIDA, USA
Karlene Garrow 05/30/2019	Slank J. Ning 5/30/19
Marlene Garrow Date Group Leader	Alexander J. Nicol Date Notary Public

Notary Public stamp with expiration date

ALEXANDER J. NICOL State of Florida-Notary Public Commission # GG 240196 My Commission Expires July 19, 2022