



## **Storage and Handling Recommendations For DMI H-Shield Roofing Products**

Dimensional Metals Polyiso products are shipped to the jobsite protected by a plastic shrink wrap and then a plastic bag. This factory packaging is intended for handling of the DMI Polyiso in the manufacturing plant and during transit. This double layer of protection has allowed DMI to ship our Polyiso products without requiring tarps for up to 700 hundred miles.

To minimize jobsite storage, we recommend delivery of DMI Polyiso products be carefully coordinated with the construction schedule. When jobsite storage is required we recommend storing the pallets of DMI Polyiso on a solid flat foundation and elevate a minimum of 2" above the finished surface. We do not recommend storing pallets of DMI Polyiso on grass or dirt areas.

Additional jobsite storing recommendations:

- Slit the bundle packaging vertically down the center of the two short sides to prevent moisture accumulation within the package
- Completely cover the bundle with a waterproof tarp and secure to prevent wind damage and/or displacement.
- Exercise care during handling to prevent breaking, edge damage or crushing of DMI Polyiso.
- Techniques such as pushing pallets off the truck, rolling pallets across the ground or roof surface, and dislodging support feet, must be avoided.

In roofing application, DMI Polyiso insulation that has become damaged, cupped, or bowed should not be installed. Apply only as much DMI Polyiso as can be covered by the finished roofing material that same day.

58 Klema Drive North – Reynoldsburg, OH 43068  
Phone 800.828.1510 Fax 740.927.3319  
[www.dmimetals.com](http://www.dmimetals.com)

***Proven. Dependable. Sustainable.***  
**Metal Envelope Systems since 1988**